




Progress of work :	Built
Dam's owner:	EDF
Consultant and physical model laboratory:	EPFL-LCH
Contractor:	Razel / Alpharoc
PKW location:	On a gravity wall extending the abutment dam
Downstream energy dissipation type:	Spillway chute
PKW purpose:	Increase discharge capacity
PKW discharge capacity at MWL (m3/s):	90
Surveillance devices (Presence and type):	No
Aeration (type and diameter of the pipe):	PEHD pipe of 160 mm of diameter
Overflowing Frequency:	Annual
Number of overflow known:	1 to 10
Maximum head on PKW experienced (m) and date:	Unknown
Material of the PKW:	Reinforced concrete
Type of model used:	Physical
Type and number of other spillway:	4 uncontrolled spillways
В (т):	9.96
P (m):	3
W (m):	16.5
L (m):	86.74
Number of inlet:	3
<i>W<sub>i</sub></i> ( <i>m</i> ):	2.3
Number of outlet:	4
<i>W<sub>o</sub></i> (m):	1.5
<i>T<sub>s</sub> (m):</i>	0.35



Plan view of the PKW



Upstream view of the PKW



Comment:

A side channel spillway had to be built because it was undesirable to pass flood water over the dam